

**BRUHAT BANGALORE MAHANAGARA PALIKE****DASARAHALLI ZONE**

Office of the Executive Engineer Dasarahalli Division  
**SCHDULE-B**

**Name of Work: Construction of Compound wall to Indira Canteen in Dasarahalli  
Ward No 15**

| Sl | Description of Work                                                                                                                                                                                                                                                                                                                                                                                                | Unit | Qty   | Sanctioned Rates |                                                                          |
|----|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-------|------------------|--------------------------------------------------------------------------|
|    |                                                                                                                                                                                                                                                                                                                                                                                                                    |      |       | In figures (Rs)  | In Words (Rs)                                                            |
| 1  | 2                                                                                                                                                                                                                                                                                                                                                                                                                  | 3    | 4     | 5                | 6                                                                        |
| 1  | Excavation for road, drains and similar works - Earthwork excavation by manual means in <b>Ordinary soil</b> involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.                                | Cum  | 64.80 | 203.13           | Rupees Two hundred Three & Thirteen Paise Only                           |
| 2  | Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. | Cum  | 8.10  | 5256.36          | Rupees Five thousand two hundred fifty six & Thirty six Paise Only       |
| 3  | Providing and constructing granite/trap/basalt size stone masonry in foundation in cement motor 1:6, Stone hammered dressed in courses not less than 20 cms high. Bond stones at two m apart in each course including cost of materials, labour, curing including cost of materials, labour, curing complete as per specifications                                                                                 | Cum  | 19.44 | 4521.96          | Rupees Four Thousand Five hundred twenty one & Ninty six Paise Only      |
| 4  | Providing and constructing granite/trap/basalt size stone masonry in Basement with cement motor 1:6, edges of Stones chistle dressed in courses not less than 15 cms high. Bond stones at two m apart in each course including cost of materials, labour, curing including cost of materials, labour, curing complete as per specifications                                                                        | Cum  | 10.94 | 5405.40          | Rupees Five Thousand Four hundred five & Forty Paise Only                |
| 5  | Providing ruled pointing 20 mm deep to coursed stone masonry with cement mortar after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.                                                                                                                                                                                                    | Sqm  | 64.80 | 105.84           | Rupees One hundred five & Eighty four paise Only                         |
| 6  | Providing and laying in position plain cement concrete of mix M1:2:4 with cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.  | Cum  | 3.65  | 5876.28          | Rupees Five thousand Eight hundred Seventy Six & Twenty eight paise Only |

Signature of the Contractor  
KRIIDL, BBMP DIVISION  
BENGALURU-560 010

*Not certified*

Executive Engineer

|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |     |        |          |                                                                        |
|---|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|--------|----------|------------------------------------------------------------------------|
| 7 | Y'hana Soudha Grill                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Sqm | 102.60 | 11600.00 | Rupees Eleven thousand Six hundred Only                                |
| 8 | Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Sqm | 105.48 | 88.56    | Rupees Eighty eight & Fifty Six Paise Only                             |
| 9 | Providing and fixing M.S. Gate as per Chief Architect Drawing, using 50mm x 50mm 14 guage M.S. hollow pipe frame work bent to ornamental shape as shown in the drawing and 35mm x 6mm and 16 x 16mm Square rods for verticals alternatively spaced at 4cms c/c in two halves and 40mmx6mm M.S. flats for horizontal member and at the top cast iron spikes are provided at alternate vertical members as shown in the drawing etc., complete. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, with lead and lift, loading and unloading charges, etc., complete as per specification. | Sqm | 2.88   | 3168.72  | Rupees Three thousand one hundred sixty eight & Seventy two Paise Only |

  
**EXECUTIVE ENGINEER**  
 Signature of the Contractor  
**BENGALURU-560 010**

  
 Executive Engineer